


**PLAN VIEW**



**PROFILE VIEW**

**NOTES:**

1. MANHOLES WITH A DEPTH OF 5 VF OR LESS SHALL USE A 2'-0" CONCENTRIC CONE SECTION.
2. IF MANHOLE DEPTH EXCEEDS 20 VF WALL THICKNESS SHALL BE 6 INCHES.
3. CURVATURE OF INVERT TO HAVE LARGEST POSSIBLE RADIUS.
4. CONCRETE SHALL BE POURED TO THE SPRING LINE OF THE PIPE (PRECAST ONLY).
5. THE RING SHALL BE ANCHORED IN A MINIMUM OF 4 PLACES BY USE OF HITI ANCHORS OR APPROVED EQUAL.
6. REFERENCE AUD DETAIL 4.10 FOR CONCRETE FOR COLLAR VALVE AND MANHOLE ON SITE
7. NO MORE THAN 6" ADJUSTMENT BY RISERS ON RING AND COVER.

NO REVISION OR MODIFICATION OF THIS DETAIL SHALL BE MADE WITHOUT PRIOR WRITTEN APPROVAL FROM AUGUSTA UTILITIES DEPARTMENT.

**APPROVED JAN. 2020**

REVISED: JANUARY 2018

**DOGHOUSE MANHOLE**

**AUGUSTA UTILITIES DEPARTMENT  
452 WALKER STREET, SUITE 200  
AUGUSTA, GA 30901**

**AUD DETAIL 2.5**

